

**Hyde-Stone Mechanical Contractors**

22962 Murrock Circle  
 Watertown, NY 13601  
 Fax

<p><b>To:</b> Village of Copenhagen                  PO Box 237                   Copenhagen, NY 13626</p>	<p><b>QUOTATION</b></p> <p>Quote #: 0000001860-000 (Preview)                  Quote Type: Work Order                  Reference: WTP Boiler Replacement                  Cross Ref:                  Work Order: n/a                  Customer: 162                  Terr/sale: WATN                  Current Date: Jun 29, 2022                  Expiry Date: N/A</p>
<p><b>Work Address:</b> Water Treatment Plant                   Copenhagen, NY                  13626</p>	

Code	Description	Quantity	UOM	Price	Total
<p>We are pleased to have the opportunity to quote you to supply/install a new boiler to replace the existing Weil McLain (wall hung) Boiler.                      We are proposing to disconnect, remove &amp; dispose of the existing boiler to include the glycol.                      We will then install the new Boiler (Manufacturer NTI Trinity Fire Tube) High Efficiency.                      We will make electrical, vent piping, gas piping transitions.                      We will flush system and install new glycol into the system.                      Once the install is complete, we will perform Manufacturer Start-up</p>					
TECH	Technician				
N/A	NTI Trinity High Efficiency Boiler				
N/A	Glycol				
N/A	Electrical Transitions				
N/A	Gas Piping Transitions				
N/A	Venting Transitions				
N/A	Misc. Material				7,960.00
<b>Sub Total</b>					7,960.00
<b>Total Quotation</b>					7,960.00

Clemons Plumbing and Heating

Clemons Plumbing and Heating  
 9997 NYS Route 26  
 Lowville, NY 13367

# Estimate

Date	Estimate #
6/16/2022	51

Name / Address
Village of Copenhagen PO BOX 237 Copenhagen, NY 13626

Project

Description	Qty	Rate	Total
All labor and material to replace LP Gas hot water boiler at pump station on Stodard Road. TO INCLUDE: 1 Weil Mclain GV90 PLUS LPGAS hot water boiler, Main building circulator, outside temperature control to shut down system in warn weather, floor mounted expansion tank, reduced pressure back flow preventer, low water cut off, pvc exvaust and combustion air piping and relocating combustion air intake, Copper supply and return piping and isolation valves, condensation piping , gas piping ,wiring, brass piping on unit heater in hypoclor injection room,removal and disposal of old equipment. All equipment made in the USA. Quote good for ten days as prices are changing daily.	1	14,000.00	14,000.00
Sales Tax		8.00%	0.00
		<b>Total</b>	<b>\$14,000.00</b>

# ONTARIO HVAC SOLUTIONS

Date: March 18, 2022

Bid: Replace Boiler at Village Water Treatment Plant

Customer: Village of Copenhagen

Dave,

Presented below is our price to install one new boiler for the Village Water Treatment Plant in Copenhagen.

## **Scope of Work:**

- Remove and dispose of existing boiler
- Provide and install one new boiler sized to match existing boiler
- Modify and reconnect to existing heating piping
- Modify and reconnect exhaust and intake piping
- Provide and install four new line voltage thermostats
- Connect thermostats and existing power wiring
- Test and start Boiler and thermostats to verify proper function
- Provide Certified Payroll Reports
- 1 year parts and Labor Warranty

**Furnace Install Price: 8,910.00**

## **Exclusions:**

Sales Tax – Assuming Village is Tax Exempt

Asbestos or hazardous material removal

If you have any questions please feel free to contact me at 315-778-9858.

Regards,

Bill Lawler  
Vice President  
Ontario HVAC Solutions, Inc.